



15-069-20587-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1973

CONSERVATION DIVISION
Wichita, Kansas

2-5-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wilmer Dreiling of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: National Oil Company,

Complete Address: Garvey Building, Wichita, Kansas.

Lease Name: Korb Well No. 1

Location: CSE-SW Sec. 27 Twp. 7 Rge. (E)(W) 22

County: Graham Total Depth 3802' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

265'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 625'.

Circulate hole with heavy mud. Pull DP to 850' and displace 105 Cu. Ft. cement thru DP. Pull DP to 270' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. E. Nichols
Conservation Division Agent