



19-069-60100-00-01

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 14 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 7-14-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Delbert Adams of Forbes Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Adams guarantees payment of the plugging fee.

Operator's full Name: Charles L. Carlock,

Complete Address: 1515 Hillcrest, Newton, Kansas.

Lease Name: DePrad Well No. 1

Location: NW-NE Sec. 27 Twp. 7 Rge. (E)(W) 22

County: Graham Total Depth 3777' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Adams was instructed to plug the well as follows:

201'--8 5/8" Surface casing, cement circulated with 260 Sx.
3770'--4 1/2" Production casing cemented on bottom with 220 Sx. Top of cement @ 3000'--(Temp. Survey). Well plugged back to 3600'. Top perforations @ 3450'.

Push plug to 3300', build sand bridge to 3280' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 130 Sx. cement, staged.

Very truly yours,

M. L. Nichols
 Conservation Division Agent