



15-065-00755-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1972
CONSERVATION DIVISION
Wichita, Kansas
11-6-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Helberg of Helberg Oil Company has this
date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: A. D. Worcester,

Complete Address: 318 East Cedar, Hill City, Kansas.

Lease Name: Worcester Well No. 4

Location: SW-SW-NW Sec. 23 Twp. 7 Rge. (E)(W) 22

County: Graham Total Depth 750' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Helberg was instructed to plug the well as follows:

150'--8 5/8" Surface casing, cement circulated.
This well was an attempted wash-down, in surface casing encountered junk
iron, wood and drilling cable, after reaching 750' elected to abandon hole.

Circulate heavy mud from TD, pull DP to 250' and displace 25 Sx. cement
thru DP. Pull DP, set bridge @ 30' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

Very truly yours,

H. L. Daniels
Conservation Division Agent