

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-065-02426-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 55-58

LOCATION SW SE SW

SEC. 17 TWP. 7 RGE. 25

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Goodrow

Operator Continental Oil Co Address Pox 98 Plainville, Kans

Field _____ County Graham

Total Depth 5950 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 240' circulated with cement - 5 1/2" 5929' with 200 sax
cement behind - P. B. to 5885', perforated 5868' 5711',

Sand to 5700', set 4 sax cement with dump bailer, pulled 1725'

5 1/2" to 1100', circulated hole with heavy mud (35 sax Gel), displaced

25 sax cement through 5 1/2" at 800', heavy mud to 225', displaced 20

sax cement through 5 1/2" at 225', heavy mud to 35', set rock and 10

sax cement to bottom cellar.

District Conservation Agent

Date 10-12-57

10-21-57
RECEIVED
OCT 21 1957
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC. 17 T. 7 R. 25W
BOOK PAGE 53 LINE 38