

KANSAS

Form CP-3
Rev. 6-26-62

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20157-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1968
CONSERVATION DIVISION
Wichita, Kansas
7-15-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Kendall Well No. 1

Location N/2-N/2-NW/4 Sec. 20 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #186, Great Bend, Kansas. License No.

Operation Completed: Hour 9:30 AM Day 11 Month 7 Year 1968

The Above well was plugged as follows:

310'--8 5/8" Surface pipe, cement circulated with 200 Sx.
Top of Dakota section @ 1070'.

Circulated hole with heavy mud. Pulled DP to 1295' and displaced 100 Sx. cement thru
DP from 1295' to 970'. Pulled DP to 330' and displaced 20 Sx. cement thru DP from
330' to 270'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 7-15-68
INV. NO. 8116-W