

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-00802-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1963
2-20-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name C & G Drilling Co.,

Complete Address: 107 Rule Building, Wichita, Kansas.

Lease Name Goodrow Well No. 1

Location SW-SW-SW Sec. 17 Twp. 7 Rge. (E) (W) ^{25 W} ₂₇

County Graham Total Depth 3920

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.,

Address: Box #486, Ellinwood, Kansas. License No. 462

Operation Completed: Hour 5 PM Day 15 Month 2 Year 1963

The Above well was plugged as follows:

277' 8 5/8" Surface w/ 185 Sx cement, cement circulated. 5 1/2" set @
3918' w/150 Sx Poz-Mix. 2-Stage w/100 Bbl. Black Magic from 2160' to
surface.

Sanded well back to 3900', set 4 Sx cement w/dump bailer. Pulled 5 1/2"
to 550', circulated heavy gel mud and displaced 20 Sx cement thru 5 1/2".
Pulled 5 1/2" to 270', displaced 20 Sx cement thru 5 1/2". Pulled casing
set bridge and 10 Sx cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 2/20/63

INV. NO. 6616-W

Signed: H. L. Nichols
Well Plugging Supervisor