

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-069-20234-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1969
CONSERVATION DIVISION
Wichita, Kansas
6-30-69

Operator's Full Name Tilco et al.
Complete Address 815 Wichita Plaza Building, Wichita, Kansas.
Lease Name Clark Well No. 1
Location SE-NE-NE Sec. 20 Twp. 7 Rge. (E) (W) 25
County Graham Total Depth 3930'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Leben Drilling, Incorporated.
Address Box #186, Great Bend, Kansas. License No.
Operation Completed: Hour 7:00 PM Day 25 Month 6 Year 1969

The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1050'.
Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru
DP from 1275' to 950'. Pulled DP to 360' and displaced 20 Sx. cement thru DP from 360'
to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 7-1-69

INV. NO. 20-W