

⁷⁰
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

15-065-02961-00-00

JUL 1 1963

7-1-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name C & G Drilling Company,

Complete Address: 107 Rule Building, Wichita, Kansas.

Lease Name Kendall Well No. 1

Location NE-NE-NW Sec. 20 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3944

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith Pipe Pulling Company,

Address: 204 E. 6th, Ellinwood, Kansas License No. 396

Operation Completed: Hour 5:30PM Day 26 Month 6 Year 1963

The Above well was plugged as follows:

290'--8 5/8" Surface pipe, cement circulated with 175 Sx.
3944'--5 1/2" cemented with 175 Sx. Plugged back to 3723'. Top of perforations
@3713'.
Sanded well back to 3705' and set 5 Sx cement with dump bailer. Pulled 5 1/2"
to 540', circulated heavy gel mud, (19 Sx Gel) and displaced 20 Sx cement
thru casing. Pulled 5 1/2" to 280', displaced 20 Sx cement thru casing. Pulled
5 1/2" @ 35'
5 1/2", set bridge/and 10 Sx cement to bottom of cellar.

I hereby certify that **INVOICED** the above well was plugged as herein stated.

DATE 7/1/63

INV. NO. 4346-W

Signed: N. L. Nichols
Well Plugging Supervisor