

KANSAS

Form CP-3
Rev. 6-9-67

JP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20167-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
CONSERVATION DIVISION
DEC 7 1967
12-7-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Halliburton Oil Producing Company,

Complete Address 520 Cameron Building, Oklahoma City, Oklahoma. 73106

Lease Name H. A. Moore Well No. 1

Location NE-NE-SE Sec. 26 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3940'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor C and G Drilling Company,

Address 107 Rule Building, Wichita, Kansas. License No.

Operation Completed: Hour 9:00 AM Day 2 Month 12 Year 1967

The above well was plugged as follows:

274'--8 5/8" Surface casing, cement circulated with 200 Sx.
Dakota section from 990' to 1175'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 880'. Pulled DP to 300' and displaced 25 Sx. cement thru DP from
300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 12/7/67
INV. NO. 6858-W