


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

ROOKS

County. Sec. 12 Twp. 8 Rge. 18 (E) W (W)

Location as "NE/CNW*SW*" or footage from lines. NE SE SE
Lease Owner C-G DRILLING CO.
Lease Name MADDY #1 Well No. _____
Office Address 1107 UNION NATIONAL BLDG, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed APRIL 11, 1968 19____
Application for plugging filed APRIL 11, 1968 19____
Application for plugging approved APRIL 11, 1968 19____
Plugging commenced APRIL 11, 1968 19____
Plugging completed APRIL 11, 1968 19____
Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well LEO F MASSEY, HAYS, KANSAS 67601
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3427 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	176.24'	NONE


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED WITH HEAVY MUD TO 720'. SET PLUG. PUT IN 70 SACKS CEMENT. FILLED WITH HEAVY MUD TO 150'. SET PLUG. PUT IN 20 SACKS CEMENT. FILLED WITH HEAVY MUD UP TO 40'. SET PLUG. FILLED TO TOP WITH 1/2 SACK HULLS AND 10 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1968
CONSERVATION DIVISION
Wichita, Kansas
04-24-1968

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G DRILLING CO
Address 1107 UNION NATIONAL BUILDING, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G F GALLOWAY (~~employee~~ or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) G F GALLOWAY 1107 UNION NATIONAL BLDG. (Address)



15th day of APRIL, 1968

Phyllis Buchanan
PHYLLIS BUCHANAN Notary Public.

15-163-20102-00-00

W E L L L O G

OPERATOR: C-G DRILLING COMPANY

WELL NAME: MADDY #1

LOCATION: NE SE SE SEC 12-8-18W

COUNTY: ~~PAWNEE~~ ^{ROOKS} COUNTY

STATE: KANSAS

WELL COMMENCED: APRIL 4, 68

WELL COMPLETED: APRIL 11, 68

ELEVATION: 1954 KB

TOTAL DEPTH: 3427'

PRODUCTION: DRY & ABANDONED

RIG NO: 1

CASING - 8-5/8": 176.24' , 5 jts. W/125 SACKS QUICKSET

5-1/2": _____

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
320	788	SHALE & SAND	1/4° 500'	
788	1039	SAND	1-1/4° 1040'	DST #1 2809-2829'
1030	1200	SHALE & RED BED	1-1/4° 1540'	DST #2 3115-3190'
1200	1322	RED BED	1° 1990'	DST #3 3308-3350'
1322	1363	ANHYDRITE	1-1/2' 2515'	
1363	2056	SHALE & SHELLS		
2056	2150	SHALE		
2150	2490	LIME & SHALE		
2490	2685	SHALE & SHELLS		
2685	3110	LIME & SHALE		
3110	3395	LIME		

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1968
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By [Signature]

SUBSCRIBED AND SWORN TO, BEFORE ME, This 15th day of April, 1968.

MY COMM. EXP. DEC. 7, 1971

[Signature]
PHYLLIS BUCHANAN - NOTARY PUBLIC

