

15-163-01052-00-00

WELL PLUGGING RECORD


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
101 No. Broadway
Wichita, Kansas

Rooks County. Sec. 12 Twp. 8S Rge. (E) 18 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Graybol Oil Corporation
Lease Name Byerly Well No. 1
Office Address 2200 N. B. T. Bldg., Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 26 19 62
Application for plugging filed July 27 19 62
Application for plugging approved July 25 19 62
Plugging commenced July 27 19 62
Plugging completed July 27 19 62
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 3480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	Salt water	3122	3333	8 5/8"	179	None
Arbuckle	Tight	3426	3480			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud-laden fluid. Pumped 20 sacks cement through drill pipe @ 550'. Pumped 20 sacks cement @ 175' and 10 sacks cement to top of surface pipe.

RECEIVED
STATE CORPORATION COMMISSION
AUG 3 1962
08-03-1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graybol Oil Corporation
Address 2200 N..B. T. Bldg., Tulsa, 3, Oklahoma

STATE OF OKLAHOMA, COUNTY OF Tulsa, ss.
Lyman C. Dennis (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lyman C. Dennis
Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 62

My commission expires October 8, 1962
Jan Lawhorn Notary Public.



GRAYBOL OIL CORPORATION

Rooks County, Kansas

No. 1 Byerly SW SW SW

Section 12-8S-18W

Contractor: Company Tools

Elev: K.B. 1930', D.F. 1930',
G.L. 1924'

Commenced: July 16, 1962

Completed: July 26, 1962

Production: Dry & Abandoned

CASING RECORD

179' 8 5/8" cemented with 130 sacks cement

Depth

Formation

184-385	Shale
385-1185	Shale and Shells
1185-1307	Red bed and shale.
1307-1346	Anhydrite
1346-1802	Shale and Shells
1802-2145	Lime and Shale.
2145-2260	Lime
2260-2980	Shale and Lime
2980-3020	Lime
3020-3121	Shale and Lime
3121-3150	Lime
3150-3208	Lime and Shale
3208-3340	Lime
3340-3400	Lime and Shale
3400-3415	Lime and Chert
3415-3432	Lime, Chert, and Sand.
3432-3480	Arbuckle Lime

E-Log Tops:

Topeka	2870
Heebner	3082
Toronto	3105
Lansing KC	3124
Base/K.C.	3347
Arbuckle	3426

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1962

CONSERVATION DIVISION
Wichita, Kansas

8/3/1962

Driller's T. D. 3480'

Welex T. D. 3480'

I hereby certify that the above is a true and correct log of the above captioned well as taken directly from the daily drilling reports.

GRAYBOL OIL CORPORATION

By: Edward Haddad
Edward Haddad, Geologist

STATE OF OKLAHOMA)
)
COUNTY OF TULSA)

Subscribed and sworn to this 1st day of August, 1962.

My commission expires: October 8, 1962

John Lawrence
NOTARY PUBLIC