

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23,047-00-00

LEASE NAME Pittman

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2310 Ft. from S Section Line

1650 Ft. from E Section Line

LEASE OPERATOR Sho-Bar Energy, Inc.

SEC. 20 TWP. 8S RGE. 18 ~~0000~~ (W)

ADDRESS P. O. Box 217, Harper, KS 67058

COUNTY Rooks

PHONE#(316) 896-2710 OPERATORS LICENSE NO. 7744

Date Well Completed 7-03-89

Character of Well D&A

Plugging Commenced 7-03-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-04-89

The plugging proposal was approved on 7-04-89 (date)

by State Plugger, Herb Dines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3512'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	305'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Circulate heavy mud in hole. 1st plug from 3475' to 3395' w/20 sx. 2nd plug from 1475' to 1395' w/20 sx. 3rd plug from 825' to 425' w/100 sx. 4th plug from 355' to 195' w/40 sx. 5th plug from 40' to surface with wiper plug w/10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel, 2% Flocel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 8-18-89

Address 150 N. Main, Suite 801, Wichita, KS 67202

STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sho-Bar Energy, Inc. AUG 10 1989

STATE OF Kansas COUNTY OF Sedgwick, ss.

CONSERVATION DIVISION
Wichita, Kansas

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

150 N. Main, Suite 801

(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 89

Sharan J. Branstetter
Sharan J. Branstetter Notary Public
Commission Expires: May 18, 1993

