


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 29 Twp. 8S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines NE SE SW
Lease Owner Peel-Hardman Oil Producers
Lease Name Stamper Well No. 1
Office Address P. O. Box 359, Hoisington, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 5-3 19 54
Application for plugging filed May 7 19 54
Application for plugging approved May 7 19 54
Plugging commenced May 15 19 54
Plugging completed May 21 19 54
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3415 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	187	8 5/8"	187	None
		0	3401	5 1/2"	3401	2701

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back with sand 10' in the pipe. Dumped 5 sacks of cement at bottom of hole. Shot pipe off at 2701'. Pulled pipe and mudded hole to 185'. Set rock bridge and dumped 15 sacks of cement at 185'. Finished mudding hole and dumped 10 sacks of cement at top of surface.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bert Self
Address R. R. #4, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
William Herbert (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William Herbert
P. O. Box 359, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 19 54

Marion M. Herbert
Notary Public.

My commission expires June 4, 1955

24-7868-S 3-53-20M
PLUGGING
FILE SEC 29 T 8 R 17W
BOOK PAGE 32 LINE 35

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 - 1954
CONSERVATION DIVISION
Wichita, Kansas

63-54

15-163-00665-00-00

DRILLERS' LOG

Company: Peel-Hardman Oil Producers

NE SE SW
Sec. 29, Twp. 8S, Rge. 17W,

Farm Name: Stemper Well No. 1

Total Depth: 3406'

County: Rooks,
Kansas

Comm: 4-16-54 Comp: 4-26-54

Contractor: Glenn W. Peel

Elevation:

Casing 8 5/8" 187' cem.
5 1/2" 3401' cem.

Production:

Figures below indicate bottoms of formations:

Rock and shale	189
Shale	860
Sand	1020
Shale	1280
Anhydrite	1320
Sand and shale	1640
Shale and shells	1800
Lime and shale	2230
Lime	2350
Lime and shale	2995
Lime	3070
Limed shale	3145
Lime	3406
Total depth	3406

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL

BY: Way Herbert

SUBSCRIBED AND SWORN to before me this 29th day of April, 1954.

My commission expires: June 4, 1955

Marion M. Herbert
Notary Public

Cable tools moved in 4-28-54. Finished drilling out plug 4-29-54 and acidized w/500 gals. Swabbed--only very light show of oil. Acidized w/2000 gals. Swabbed and test on 4-30-54. Got 3 gals. oil per hr. Drilled ahead to 3415. Ran Lane-Wells log. Set Lane-Wells plug at 3394. Perforated 3391-94 and acidized. Swab tested on 5-1-54. Got 36 gal. per hr, 10 gal. oil. Set LW plug @ 3360'. Perforeted w/12 shots from 3328-3332. Acidized w/2000 gals. Swab tested 5-2-54. 2 1/2 bbls. per hr., 10 gal s oil. Set LW plug @ 3260'. Perforated from 3205-09. No show. Acidized w/1000 gals. No show. Dry and abandoned 5-2-54.

PLUGGING
FILE 2918-17W
PAGE 32 LINE 35

RECEIVED
STATE CORPORATE
MAY 8 1954
CONSERVATIVE
Wichita

5-8-54