

15-163-20415-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Plat

Rooks County. Sec. 29 Twp. 8 Rge. 17 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE NW SE  
Lease Owner Black Petroleum, Inc.  
Lease Name Stamper "F" Well No. 1  
Office Address Suite 445 Garvey Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 2-10-1972  
Application for plugging filed 2-10-1972  
Application for plugging approved 2-10-1972  
Plugging commenced 2-10-1972  
Plugging completed 2-10-1972  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3,430 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	263'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill hole w/heavy mud  
Set bridge plug @600'  
Pump 70 sax cement on plug thru 4 1/2" drill pipe  
Fill hole w/heavy mud  
Set bridge plug @240'  
Pump 20 sax cement on plug thru 4 1/2" drill pipe  
Fill hole w/heavy mud  
Set bridge plug @40' w/1/2 sax hulls on plug  
Dump 10 sax cement on plug to cellar

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 25 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc. 2-25-72  
Address Shields Bldg., Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss. R. J. Shields contractor

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Shields Bldg., Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of February, 1972

My commission expires May 26, 1975 [Signature] Notary Public.



Shields


15-163-20415-00.00

Russell, Kansas

WELL LOG

Operator: Black Petroleum, Inc.  
 Well: Stamper "F" #1  
 Commenced: February 3, 1972  
 Completed: February 10, 1972  
 Contractor: Shields Drilling Co., Inc.

Well Description: Approx. SE NW SE  
 Sec. 29-8S-17W  
 Rooks Co., Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	263'	Cmtd. w/175 sax

Elevation:  
 Treatment:  
 Production: D & A  
 Tops:

..... Figures Indicate Bottom of Formations .....

Clay & Shale	215'
Shale	270'
Shale & Sand	850'
Redbed	1,195'
Shale	1,297'
Anhydrite	1,338'
Shale	1,610'
Shale & Lime	2,785'
Lime	3,036'
Lime & Shale	3,116'
Lime	3,430' RTD

2-25-72  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 25 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas

Notes