

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-00622-00-00

API NUMBER Drilled May, 1953

LEASE NAME Stamper "C"

WELL NUMBER #1

330 Ft. from ~~XX~~<sup>S</sup> Section Line

330 Ft. from ~~X~~<sup>W</sup> Section Line

SEC. 28 TWP. 8S RGE. 17W ~~XXXXXX~~(W)

COUNTY Rooks

Date Well Completed May, 1953

Plugging Commenced 12:30 P.M.  
1-19-94

Plugging Completed 3:15 P.M.  
1-19-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS P.O. Box 352, Russell, KS 67665

PHONE#(913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ District #4 \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? No - well \_\_\_\_\_ If not, is well log attached? NA

drilled prior to inception of ACO-I  
Producing Formation Lansing/KC Depth to Top 3058' Bottom 3376' T.D. 3427'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	165'	-0-
				5-1/2"	3417'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Ran 2-1/2" tubing to 3100'. Mixed 5 sks. gel - 75 sks. cement w/350# hulls. Pulled tubing to 2200'. Mixed 100# hulls w/50 sks. cement. Pulled tubing to 1200'. Mixed 60 sks. cement & circulated cement. Came out of hole w/tubing. Down 5-1/2" casing mixed 40 sks. cement, maximum pressure - 300#, shut in @ 200#. Down 8-5/8" casing mixed 50# hulls w/25 sks. cement, maximum pressure - 400#, shut in @ 200#.

Name of Plugging Contractor Allied Cementing Company, Inc. License No. \_\_\_\_\_

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III

~~XXXXXX~~ ~~Operator~~ ~~XXXXXX~~ (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John O. Farmer III


(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 2nd day of February, 19 94

Margaret A. Schulte  
Notary Public  
Margaret A. Schulte

My Commission Expires:

USE ONLY ONE SIDE OF EACH FORM



Form CP-4  
Revised 05-88