

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-03200-00-00

API NUMBER \_\_\_\_\_

LEASE NAME Russ

WELL NUMBER 1

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 29 TWP. 8 RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed 2/17/58

Plugging Commenced 10:45 A.M. 12/4/96

Plugging Completed 11:30 A.M. 12/4/96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE#(913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 4, 1996 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? Already on file

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3352

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	178'	
				5 1/2"	3344'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Perforated 3 holes @ 725'; 3 holes @ 1265' & 3 holes @ 2050'. 5 1/2" csg. - Mixed 275 sx cement w/400# Hulls @ 500# Max PSI. Shut in @ 200#.  
8 5/8" Backside - Mixed 24 sx cement w/100# Hulls @ 400# Max PSI. Shut in @ 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing co., Inc. License No. \_\_\_\_\_

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales (Employee of Operator) or (~~Operator~~) of above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dane G. Bales

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 5th day of December, 1996



Betty Jane Bittel Notary Public

My Commission Expires: July 17, 2000.