

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-01822-00-00

LEASE NAME Bird

WELL NUMBER 4

4290 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 30 TWP. 8 RGE. 17 (X) or (W)

COUNTY Rooks

Date Well Completed 10/1/55

Plugging Commenced 4/24/02

Plugging Completed 4/24/02 12:00P.M.

RECEIVED

APR 29 2002

KCC WICHITA

4-29-2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE#(784) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 24, 2002 (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation LKC/Arbuckle Depth to Top 3108 Bottom 3330 T.D. 3405

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	163'	None
				5 1/2	3393'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mixed 240 sx 60/40 10% gel w/400# hulls down 5 1/2" casing. Max Pressure 600#.
Shut in at 300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No.

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Richard L. Wallgren, Sr.

(Employee of Operator) or ~~Contractor~~ of

above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
Richard L. Wallgren, Sr.
(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 25 day of April 2002



Betty Jane Bittel
Betty Jane Bittel Notary Public

My Commission Expires: July 17, 2004.

RECEIVED

APR 29 2002

KCC WICHITA

15-163-01822-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN WELL NAME BIRD #4

WELL LOCATION SW NE NW Sec. 30-8-17W RIG #1

COUNTY ROOKS STATE KANSAS

COMMENCEMENT DATE SEPTEMBER 22, 1955 COMPLETION DATE OCTOBER 1, 1955

LOG OF WELL

Elevation 1973 rotary bushing.
All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	163	Sand-Shale		
163	825	Sand-Shale		
825	1000	Sand		
1000	1135	Red Bed		
1135	1296	Red Bed		
1296	1336	Anhydrite		
1336	1640	Shale-Shells		
1640	1875	Shale-Shells		
1875	2050	Lime-Shale		
2050	2175	Lime-Shale		
2175	2350	Lime-Shale		
2350	2450	Lime-Shale		
2450	2550	Lime-Shale		
2550	2630	Lime-Shale	0° - 2500'	
2630	2790	Lime-Shale	0° - 2750'	
2790	2915	Lime-Shale		
2915	2975	Lime-Shale		
2975	3025	Lime-Shale	0° - 3000'	
3025	3080	Lime-Shale		
3080	3117	Lime-Shale		
3117	3140	Lime-Shale		DST 3093-3117'
3140	3152	Lime-Shale		DST 3129-40'
3152	3215	Lime-Shale		
3215	3252	Lime-Shale		
3252	3286	Lime-Shale	0° - 3250'	
3286	3303	Lime-Shale		DST 3278-86'
3303	3345	Lime-Shale		
3345	3396	Lime-Shale		

CASING LEFT IN HOLE AFTER COMPLETION

163' of 8-5/8" OD Surface Casing.
Ran 3397.41' (101 jts.) of 5-1/2" OD Casing.
STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

RECEIVED

OCT 8 1955

D. G. Hansen, Notary Public

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway
Jay H. Galloway

Subscribed and sworn to before me this 26th day of October, 1955.

Vicky Jacobs
Vicky Jacobs, Notary Public

My commission expires:
May 20, 1959