


Giv. All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks _____ County. Sec. 30 Twp. 8 Rge. 17 (E) _____ (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Okmar Oil Company
Lease Name Snyder Well No. 1
Office Address 1130 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Dry Hole
Date well completed June 19 59
Application for plugging filed July 19 59
Application for plugging approved July 19 59
Plugging commenced July 16, 19 59
Plugging completed July 22, 19 59
Reason for abandonment of well or producing formation Could not make well

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3416 Bottom 3430 Total Depth of Well 3430 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8"	177	
				4 1/2"	3429	2824

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 3260' to 3130' and run 4 sacks cement from 3130' to 3090' working 15" tension in 4" pipe. Shot at 3085' 2984' and spotted oil at 2984'. Working 31" tension in 4" pipe and shot at 2945'. Working 3 1/4" tension in 4" pipe, shot at 2852' and started 4" pipe. Pulled pipe. Pumped in mud at 480' and 20 sacks of cement at 480' pumped 20 sacks of cement at 160' and run 10 sacks cement cap to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 20 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Box 114, Ellinwood, Kansas

S-20-64

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Robert M. Beren (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert M. Beren

1130 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of May, 19 64

Jeannine Reszue
Notary Public.

My commission expires March 12, 1966

