

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-19020-00-01

Original
API NUMBER D&A May 1958
SWD comp. 6/65
LEASE NAME Russ
WELL NUMBER 2

RECEIVED
11-13-2001
NOV 13 2001

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3630 Ft. from S Section Line
990 Ft. from E Section Line

KCC WICHITA

LEASE OPERATOR The Dane G. Hansen Trust

SEC. 30 TWP. 8s RGE. 17 (E) or (W)

ADDRESS P. O. Box 187, Logan, Kansas 67646

COUNTY Rooks

PHONE#(785) 689-4816 OPERATORS LICENSE NO. 5285

Date Well Completed 6/10/65

Character of Well SWD

Plugging Commenced 2:00 P.M. 11/6/01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2:45 P.M. 11/6/01

The plugging proposal was approved on November 6, 2001 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.D. 3754

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	169'	None
				5 1/2	3454'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mixed 300 sx 60/40 poz, 10% Gel with 500# hulls down 5 1/2".

Max psi 150. Cement fill back to 750' from surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No.

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Richard L. Wallgren, Sr. (Employee of Operator) ~~xxxx(Operator)~~ of

above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L. Wallgren, Sr.

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 8 day of November, 2001



My Commission Expires: July 17, 2004. Betty Jane Bittel

RECEIVED

11-13-2001

NOV 13 2001

CONTRACTOR KCC WICHITA LOG

15-163-19020-00-01

OPERATOR D. G. Hansen

WELL NAME Russ #2

LOCATION NW SE NE SEC. 30-8-17W

RIG NO. 1

COUNTY Rooks

STATE Kansas

COMMENCEMENT DATE April 25, 1958

COMPLETION DATE May 3, 1958

LOG OF WELL

Elevation 1944' kelly bushing.

All measurements taken from the top of kelly bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	169	Sand-Shale		
169	485	Sand-Shale		
485	600	Sand		
600	750	Sand-Shale		
750	950	Sand		
950	1275	Red Bed		
1275	1276	Red Bed		
1276	1312	Anhydrite		
1312	1815	Shale-Shell		
1815	2075	Shale-Shell		
2075	2200	Lime-Shale		
2200	2340	Lime-Shale		
2340	2515	Lime-Shale	0° - 2500	
2515	2690	Lime-Shale		
2690	2855	Shale-Lime	0° - 2750	
2855	2952	Lime-Shale		
2952	3060	Lime-Shale	0° - 3000	
3060	3100	Lime-Shale		
3100	3135	Lime-Shale		DST 3075-3100'
3135	3202	Lime		
3202	3213	Lime-Shale		DST 3177-3202'
3213	3265	Lime	0° - 3250	DST 3204-3213'
3265	3300	Lime		DST 3264-3300'
3300	3325	Lime-Shale		
3325	3342	Lime		
3342	3375	Lime-Shale		
3375	3435	Lime-Shale		
3435	3440	Lime-Shale		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 169.98' (9 jts.) 8-5/8" OD Surface Casing.

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. P. Galloway
G. P. Galloway

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6th day of May, 1958.

Vicky Jacobs
Vicky Jacobs, Notary Public

My commission expires: May 20, 1959