


15-163-19020-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec 30 Twp. 8 Rge. 17W (E) (W)
Location as "NE/CNW%SW%" or footage from lines NW SE NE
Lease Owner D. G. Hansen
Lease Name Russ Well No. 2
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 3 1958
Application for plugging filed May 3 1958
Application for plugging approved May 3 1958
Plugging commenced May 3 1958
Plugging completed May 3 1958
Reason for abandonment of well or producing formation Too low structurally



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3440 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|---------|------------|
| | | | | 8-5/8" | 169.98' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 450'. Set plug. Put in 20 sacks cement. Filled to 160'. Set plug. Put in 15 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co. 5-17-58
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of May, 1958

My commission expires May 20, 1959

Vicky Jacobs
Vicky Jacobs Notary Public.

PLUGGING
FILE SEC 30 T. 8 R. 17W
BOOK PAGE 100 LINE 6

15-163-19020-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen WELL NAME Russ #2
 LOCATION NW SE NE SEC. 30-8-17W RIG NO. 1
 COUNTY Rooks STATE Kansas
 COMMENCEMENT DATE April 25, 1958 COMPLETION DATE May 3, 1958

LOG OF WELL

Elevation 1944' kelly bushing.
 All measurements taken from the top of kelly bushing.

| FROM | TO | FORMATION | DEVIATION FROM VERTICAL | REMARKS: |
|------|------|-------------|-------------------------|----------------|
| 0 | 169 | Sand-Shale | | |
| 169 | 485 | Sand-Shale | | |
| 485 | 600 | Sand | | |
| 600 | 750 | Sand-Shale | | |
| 750 | 950 | Sand | | |
| 950 | 1275 | Red Bed | | |
| 1275 | 1276 | Red Bed | | |
| 1276 | 1312 | Anhydrite | | |
| 1312 | 1815 | Shale-Shell | | |
| 1815 | 2075 | Shale-Shell | | |
| 2075 | 2200 | Lime-Shale | | |
| 2200 | 2340 | Lime-Shale | | |
| 2340 | 2515 | Lime-Shale | 0° - 2500 | |
| 2515 | 2690 | Lime-Shale | | |
| 2690 | 2855 | Shale-Lime | 0° - 2750 | |
| 2855 | 2952 | Lime-Shale | | |
| 2952 | 3060 | Lime-Shale | 0° - 3000 | |
| 3060 | 3100 | Lime-Shale | | DST 3075-3100' |
| 3100 | 3135 | Lime-Shale | | |
| 3135 | 3202 | Lime | | DST 3177-3202' |
| 3202 | 3213 | Lime-Shale | | DST 3204-3213' |
| 3213 | 3265 | Lime | 0° - 3250 | DST 3264-3300' |
| 3265 | 3300 | Lime | | |
| 3300 | 3325 | Lime-Shale | | |
| 3325 | 3342 | Lime | | |
| 3342 | 3375 | Lime-Shale | | |
| 3375 | 3435 | Lime-Shale | | |
| 3435 | 3440 | Lime-Shale | | |

RECEIVED
STATE OF KANSAS COMMISSIONER

MAY 17 1958

CONSERVATION DIVISION
Wichita, Kansas

S-17-58

CASING LEFT IN HOLE AFTER COMPLETION

Ran 169.98' (9 jts.) 8-5/8" OD Surface Casing.

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
 G. F. Galloway

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6th day of May, 1958.

Vicky Jacobs
 Vicky Jacobs, Notary Public

My commission expires: May 20, 1959

PLUGGING
 FILE SEC 30 T 8 R 17W
 BOOK PAGE 100 LINE 6