

15-163-03654-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

Rocks _____ County. Sec. 30 Twp. 8 Rge. 17 (W) (N)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW
Lease Owner William Graham Oil Company
Lease Name Snyder Well No. 1
Office Address 204 N. Market, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed Dec. 4, 1949 19.
Application for plugging filed Dec. 4, 1949 19.
Application for plugging approved Dec. 9, 1949 19.
Plugging commenced Dec. 4, 1949 19.
Plugging completed Dec. 4, 1949 19.
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				<u>8 5/8"</u>	<u>150'</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged at 150';
Cement with 15 sacks cement.
Filled hole with rotary mud between
plugs. Top plug set at 35' and
cemented with 10 sacks

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to _____ 12-10-49

Address _____


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. A. GILLILAND (employee of owner) or (owner/lessee) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) J. A. Gilliland

204 N. Market, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of December, 19 49.

My commission expires 9-3-51 _____ Notary Public.



WELL RECORD

SNYDER #1

Location: SW SW SW
Sec. 30-8-17W
Rooks County, Kansas

Commenced: November 26, 1949

Completed: December 4, 1949

Operator: William Graham Oil Company
204 North Market
Wichita, Kansas

Production: D & A

Contractor: William Graham Oil Company
Same

Casing Record: Set 150' of 8 5/8" Surface Casing
Cemented same with 110 sacks regular cement

LOG

(Figures indicate bottom of formation)

Surface soil and clay	66		
Shells and Shale	495		
Sand	555		
Sand and shale	580		
Shale and shells	795		
Pyrite	810		
Sand	940		
Red Bed	1175		
Shale	1280		
Anhydrite	1318	Top Heebner	3094
Shale	1475	Top Kansas City Lime	3138
Shale and shells	1815		
Lime and shale	2334		
Sandy lime	2352		
Lime	2495		
Lime and shale	2875		
Lime	2960		
Lime and shale	3138		
Lime	3370		
Shale and lime	3429		
Total Depth	3429		

The undersigned, WILLIAM GRAHAM OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WILLIAM GRAHAM OIL COMPANY

[Signature]
By _____ Owner

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

DEC 10 1949 12-10-49
STATE COMMISSION

Be it remembered that on the 5th day of December, 1949 before me the undersigned, a notary public, duly commissioned in and for the County and State aforesaid, came William L. Graham, Owner of WILLIAM GRAHAM OIL COMPANY, a Partnership of the State of Kansas, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said Partnership, and he duly acknowledged the execution of the same for himself and for said Partnership.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

[Signature]
Notary Public.

My Commission Expires: Oct. 12-1953

PLUGGING
FILE SEC 30 T 8 R 7 W
BOOK PAGE 128 LINE 81