

15-163-19032-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

_____ Rooks _____ County. Sec. 30 Twp. 8 Rge. 17 (E) _____ (W) W
Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner D. G. Hansen
Lease Name Kennedy Well No. 1
Office Address Logan, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 11 19 60
Application for plugging filed July 11 19 60
Application for plugging approved July 11 19 60
Plugging commenced July 11 19 60
Plugging completed July 11 19 60
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3421 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	160.71	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 500'. Set plug. Put in 20 sacks cement. Filled to 155'. Set plug. Put in 1/2 sack hulls and 15 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.


FILED
STATE CORPORATION COMMISSION
JUL 26 1960
CONSERVATION DIVISION
WICHITA, KANSAS

RECEIVED
JUL 16 1960
D. G. HANSEN
Time.....

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G Drilling Co. 7-26-60
Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) G. F. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of July, 1960
My commission expires May 20, 1963
Vicky Jacobs
Notary Public.



15-163-19032-00-00

W E L L L O G

OPERATOR D. G. HANSEN SEC. 30-8-17W
 WELL NAME KENNEDY #1 LOC. NW NW SE
 TOTAL DEPTH 3421' COUNTY Rooks
 COMM. JULY 3, 1960 COMP. JULY 11, 1960 STATE Kansas
 RIG NO. 1 ELEVATION 1952' R.B.
 CASING: RAN 160.71' (8 jts.) 8-5/8" OD Surface Casing. PRODUCTION: O & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	797	Shale-Sand		
797	1005	Sand		
1005	1297	Red Bed		
1297	1335	Anhydrite		
1335	1770	Shale-Shell		
1770	2290	Shale-Lime	0° - 2500	
2290	2900	Lime-Shale	0° - 2750	
2900	3015	Lime	0° - 3000	
3015	3095	Lime-Shale		DST 3087-3115'
3095	3185	Lime		
3185	3225	Lime-Shale		DST 3214-3225'
3225	3325	Lime	0° - 3250	
3325	3421	Lime-Shale		

RECEIVED
CORPORATION COMMISSION

JUL 26 1960

CONSERVATION DIVISION
Wichita, Kansas

7-26-60


STATE OF KANSAS }
COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway

AND SWORN TO, BEFORE ME, THIS 15th day of July, 1960.



Vicky Jacobs - Notary public