

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 035-02077 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 12-02-1945.

Well Operator: W.D. Short Oil Co., LLC KCC License #: 33608
(Owner / Company Name)

Address: P.O. BOX 729 City: OXFORD (Operator's)

State: KANSAS Zip Code: 67119 Contact Phone: (620) 455 - 3576

Lease: RAHN UNIT #1 Well #: 5 Sec. 5 Twp. 34 S. R. 6 East West

100' W of SE - SW - NW Spot Location / QQQQ County: COWLEY

2310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

890 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 13-3/8 Set at: 160 Cemented with: 250 Sacks

Production Casing Size: 8-5/8 Set at: 2867 Cemented with: 250 Sacks

List (ALL) Perforations and Bridgeplug Sets: PERFS: 2122-2124

Elevation: 1122 (G.L. / K.B.) T.D.: 2879 PBDT: _____ Anhydrite Depth: 500'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): PER KCC REGULATIONS

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: GARRETT VANDEVER

Phone: (620) 218 - 1820

Address: P.O. BOX 729 City / State: OXFORD, KANSAS 67119

Plugging Contractor: B.P.C. Well Plugging KCC License #: 32475
(Company Name)

Address: P.O. BOX 282 BURDEN, KANSAS Phone: (620) 438 - 2856
(Contractor's)

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3-2-2006 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 07 2006
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

W.D. Short Oil Co., LLC
PO Box 729 - 102 S. River Road
Oxford, KS 67119

March 20, 2006

Re: Rahn Unit #1 (BERRY & E.S.BERRY #1) #5
API 15-035-02077-00-00
SESWNW 5-34S-6E, 2310 FNL 890 FWL
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

Sincerely,


David P. Williams
Production Supervisor

RAHN UNIT 1 NO. 17
330'N 990'W - Sec 5-34S-6E
Cowley County, Kansas

WELL RECORD

Operator: Continental Oil Company
Ponca City, Oklahoma

Contractor: Lohmann-Johnson Drilling Co., Inc.
320 Indiana Bank Building
Evansville, Indiana

Casing: Ran 209 ft. 8-5/8" Surface Pipe set at 205' w/200 Sacks
Set 2171 ft. 4-1/w" Casing w/100 Sacks

Started: May 16, 1956
Completed: May 24, 1956

L O G

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>
0	35	Surface
35	209	Lime & Shale
209	510	Shale w/Lime Streaks
510	990	Shale & Lime
990	1345	Shale, Sand & Lime
1345	1702	Shale
1702	1725	Sand
1725	1887	Shale & Lime
1887	2095	Shale
2095	2135	Core #1 - 40 ft.
2135	2175	Sandy Shale
2175		TOTAL DEPTH

*Coyote Corp
8-2-56*

RECEIVED
MAR 07 2006
KCC WICHITA

PAUL D. KOONTZ
GEOLOGIST
1954 BELMONT
EL DORADO, KANSAS 67042

July 19, 1975

MR. W. D. SHORT
P. O. Box 45
Oxford, Kansas 67119

Re: Cox 2-A, SW-SE-NW
Section 5-34S-6E
Cowley County, Kansas

Dear Sir:

This report on the subject well is based on microscopic examination of rotary cuttings from 1400' to the total depth of 2194'. All measurements were taken from the rotary drive bushing, which was 3' above derrick floor and 5' above ground level.

The following tops were picked:

Elevation RB		(+1198)
Toronto Limestone	1456	(- 258)
Douglas Shale	1473	(- 275)
Douglas Sand	1506	(- 308)
Brown Lime	1693	(- 495)
Stalnaker Sand	1721	(- 523)
Farry Sand	1938	(- 740)
Iola Limestone	2165	(- 967)
Layton Sand	2195	(- 987)
R.T.L.	2195	(- 996)
Casing Point	2186	(- 988)

Shows of oil are as follows:

STALNAKER SAND
1721-43'. Sand, grey, angular, micaceous, platy, with slight porosity, and no odor, staining or fluorescence. Does not merit testing.

1755-70'. Sand, grey to brown, mediu, angular, micaceous. Good to fair granular porosity, with light spotted staining and free oil. Fair odor, and spotted, rich to light fluorescence. Zone probably carries water, but merits testing before well is abandoned.

RECEIVED
MAR 07 2006
KCC WICHITA