
KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION



API #_ 15 - 047-20,263 -6000	(Identifier Number of this we	ell). This must be listed for wells drill	ed since 1967; if no API # was issued,	
indicate original spud or completion date 7/1977	*			
Well Operator: Oil Producers Inc. of Kansas	KCC License #:_8	KCC License #: 8061		
Address: 1710 Waterfront Parkway, Wichit			(Operator's)	
		Contact Phone: (316)	681 - 0231	
Lease: Schmitt	Well #: 2	Sec. 27 Twp. 24	S. R. <u>16</u> East ✓ West	
<u>NW</u> - <u>NE</u> - <u>SW</u> _{Spo}	ot Location / QQQQ Co	_{ounty:} Edwards		
2310' Feet (in exact footage) From	North / South (from n	earest outside section corner) Line of	Section (Not Lease Line)	
1650 Feet (in exact footage) From		earest outside section corner) Line of		
Check One:	D&A Cathodic [Water Supply Well		
SWD Docket #	ENHR Docket #		Other:	
Conductor Casing Size: None	Set at:	Cemented with:	Sacks	
Surface Casing Size: 8 5/8"	Set at: <u>307'</u>	Cemented with: 22	5 Sacks	
Production Casing Size: 4 1/2"	Set at: 4369'	Cemented with: 10	0 Sacks	
List (ALL) Perforations and Bridgeplug Sets: Mississippi 4275'-4300'				
Elevation: 2075' (G.L./ K.B.) T.D.: 4370' PBTD: 4330' Anhydrite Depth: 1450'				
(Stone Corral Formation) Condition of Well: Good Poor ✓ Casing Leak ✓ Junk in Hole				
Proposed Method of Plugging (attach a separate page if additional space is needed): Set CIBP above stuck tbg in hole @ 3190' w/ 2 sx, shoot off 4 1/2" @ 2000'				
pull up 1 jt and spot 35 sx plug, pull to 1450' w/ 50 sx plug, pull to 330' w/ 40 sx plug, pull to 30' w/ 10 sx plug, all 60/40 w/ 6% gel.				
This plug is recommended by Steve Durrant, KCC Representative-Dodge City				
	Yes ✓ No Is ACO-1			
If not explain why?				
Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission. List Name of Company Representative authorized to be in charge of plugging operations: Brad Siroky				
List Name of Company Representative authorized to	be in charge of plugging opera		- 2044	
4740 Westerfacet Designation Wielite	VC 67206	Phone: (316) 371		
Address: 1710 Waterfront Parkway, Wichita, KS 67206			_ City / State: Wichita, KS	
Plugging Contractor: Acid Services (Company Name)		KCC License #: 32453	KCC License #: (Contractor's)	
Address: 100 S. Main, STE 607, Wichita, KS 67202 Phone: (316) 262 - 3699				
Proposed Date and Hour of Plugging (if known?): 3/	15/06 Daylight			
Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent				
Date: 3/14/06 Authorized Operator /	Agent:	(Signature)		

CORPORATION COMMISSION

Kathleen Sebelius, Governor

Brian J. Moline, Chair

Robert E. Krehbiel, Commissioner

Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Oil Producers Inc. of Kansas 1710 Waterfront Parkway Wichita, KS 67206

March 22, 2006

Re: SCHMITT #2

API 15-047-20263-00-00

FSL FWL

NWNESW 27-24S-16W, 2310 FNL 1650 FEL

EDWARDS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1

210 E Frontview, Suite A

Dodge City, KS 67801

(620) 225-8888

David P. Williams

Production Supervisor