

15-163-01073-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rooks County, Sec. 27 Twp. 8S Rge. 17 (W)

Location as "NE/CNW/SE/SW" or footage from lines SE NE SE

Lease Owner ALPINE OIL & ROYALTY Co., INC.

Lease Name BEMIS Well No. 1

Office Address 800 BITTING BLDG., WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 11-17 19 64

Application for plugging filed (PHONE 11-17-64) 11-23 19 64

Application for plugging approved 11-17 19 64

Plugging commenced 11-17 19 64

Plugging completed 11-17 19 64

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well BILL NICHOLS AND ELDON PETTY

Producing formation Depth to top Bottom Total Depth of Well 3475 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	180	8-5/8	180	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 540 FEET. USED GLOVE OILWELL CEMENTING CO. PUMP TRUCK TO SET FIRST PLUG AT 540 FEET WITH HULLS AND 20 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 185'. SET SECOND PLUG AT 185 FEET WITH HULLS AND 20 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET THIRD PLUG WITH 10 SACKS CEMENT AND HULLS. PLUGGED RAT HOLE WITH 2 SACKS CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 24 1964

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor GABBERT-JONES INC. 11-24-64  
Address 514 ORPHEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

514 ORPHEUM BLDG., WICHITA, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 23RD day of NOVEMBER, 1964

My commission expires OCTOBER 2, 1967 VIRA A. MCKENZIE Notary Public.

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS WELL LOG

15-163-01073-00-00

BEMIS #1  
 SE NE SE SECTION 27-8S-17W  
 ROOKS COUNTY, KANSAS

COMMENCED: NOVEMBER 10, 1964  
 COMPLETED: NOVEMBER 18, 1964

OPERATOR-ALPINE OIL AND ROYALTY Co., INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	70	Post Rock	RAN 5 JOINTS 8-5/8" CASING, SET @ 180' w/ 150 SACKS CEMENT
70	190	SURFACE CLAY & SHALE	
190	208	SHALE & SHELLS	
208	820	SHALE & LIME	
820	875	SHALE	
875	1025	SAND	
1025	1318	SHALE & RED BED	
1318	1359	ANHYDRITE	
1359	1500	SHALE	
1500	1845	SHALE & SHELLS	
1845	2050	SHALE & LIME	
2050	2170	LIME	
2170	2750	SHALE & LIME	
2750	3457	LIME	
3475	TD		

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 24 1964  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 11-24-64  
 DRY & ABANDONED

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN THE SE NE SE SECTION 27-8S-17W, ROOKS COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall  
 E. E. HALL

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 19TH DAY OF NOVEMBER, 1964, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Vira A. McKenzie  
 VIRA A. MCKENZIE, NOTARY PUBLIC

My COMMISSION EXPIRES OCTOBER 2, 1967