

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-20364 00-00

LEASE NAME Forrest Stamper

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1-V

4950 Ft. from S Section Line

4290 Ft. from E Section Line

LEASE OPERATOR The Gene Brown Company

SEC. 20 TWP. 8 RGE. 17 (E) or (W)

ADDRESS Drawer 220 Plainville Ks. 67663

COUNTY Rooks

PHONE# (913) 434-4811 OPERATORS LICENSE NO. 5635

Date Well Completed 5-18-71

Character of Well Oil

Plugging Commenced 6-25-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-25-93

The plugging proposal was approved on June 23rd 1993 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation ARBUCKLE-LKC Depth to Top 3044 Bottom 3328 T.D. 3328

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8	249	None
Production				5 1/2	3321	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran wire line to 2400ft. Found sand from 2400 to TD. Perf casing at (2050-1250-715)
Ran tubing to 2400 and spotted 65 sks with 200# hulls. Pull tubing to 1400 and spotted
40 sks with 100# hulls. Pulled tubing to 700 and spotted 50 sks with 100#hulls. Pumped
45sks with 50# hulls down 5 1/2 casing. Max pressure 300 and shutin pressure 100. OVER
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address Russel Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Gene Brown Company

STATE OF Kansas COUNTY OF Rooks, ss.

Thomas M. Brown (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the contents, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Thomas M. Brown

(Address) Plainville Ks.

SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 93

Bonita K. Schubert
 Notary Public

My Commission Expires: July 2, 1997



Pumped 25 sks down 8 5/8. Max pressure 200 and shutin pressure at 100.
Well plugged at 12:30 pm.

WELL PLUGGED - 12:30 PM
WELL PLUGGED AT 12:30 PM