


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Re 15-163-19114-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks County, Sec. 20 Twp. 8 Rge. 17 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW SE SW  
Lease Owner D. G. Hansen  
Lease Name Russ "A" Well No. 1  
Office Address Box 195, Logan, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 10-5-60 19  
Application for plugging filed 10-3-60 19  
Application for plugging approved 10-3-60 19  
Plugging commenced 10-3-60 19  
Plugging completed 10-5-60 19  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	159'	None
				5 1/2"	3327'	2602'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand to 3310' with 4 sacks cement.  
Pumped 40 sacks jell mud, plug and 100 sacks cement.  
Filling hole from 300' to base of cellar with cement.

Mudding & Cementing by Sun Cementing Company

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc. 10-10-60  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren H. Harner

Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of October, 19 60

My commission expires 24 October 1960

Stanley W. Miller  
Notary Public.



15-163-19114-00-00

WELL LOG

OPERATOR D. G. Hansen

WELL NAME Russ "A" #1

TOTAL DEPTH 3341'

COMM. June 2, 1959

COMP. June 11, 1959

RIG NO. 1

SEC. 20-8-17W

LOC. NW SE SW

COUNTY Rooks

STATE Kansas

ELEVATION 1899' K.B.

CASING: Ran 159.82' (8 jts.) 8-5/8" OD Surface Casing.  
Set 5-1/2" OD Casing @3327' (102 jts.)

PRODUCTION: Producing

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	104	Shale-Sand		
104	790	Sand-Shale		
790	945	Sand		
945	1240	Red Bed		
1240	1274	Anhydrite		
1274	1990	Shale-Shells	0° - 2500	
1990	2280	Shale-Lime	0° - 2750	
2280	3049	Lime-Shale	0° - 3000	
3049	3105	Lime		DST 3022-3049
3105	3135	Lime-Shale		DST 3046-3072
3135	3199	Lime		DST 3082-3105
3199	3225	Lime-Shale		DST 3143-3160
3225	3292	Lime		DST 3203-3225
3292	3341	Lime-Shale	0° - 3250	DST 3224-3282 DST 3327-3341

RECEIVED  
STATE CORPORATION COMMISSION

JUL 13 1970

CONSERVATION DIVISION  
Wichita, Kansas

7-13-70

RECEIVED

JUN 23 1959

D. G. HANSEN

Time.....

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

J-G DRILLING CO.

By G. F. Galloway  
G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 15th day of June 1959

Vicky Jacobs  
Vicky Jacobs Notary public