

15-163-01367-00-00

API NUMBER _____

LEASE NAME Reeder 'A'

WELL NUMBER 1

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 20 TWP. 8S RGE. 17W(X) or (W)

COUNTY Rooks

Date Well Completed 3/26/59

Plugging Commenced 10/19/98

Plugging Completed 10/19/98 12:30P.M.

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE#(785) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 19, 1998 (date)

by Rich Williams (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation LKC Depth to Top 3034 Bottom 3156 T.D. 3328

P.B.T.D. 3322

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	175'	None
				5 1/2	3322	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
100 sx + 2 Hulls @ 2800. Pulled to 1700, mixed 110 sx + 3 Hulls and circulated
cement. Pulled tubing out. Tied on to 5 1/2, mixed 50 sx, Max 700%, Shut in
@ 200%. Tied on to 8 5/8, mixed 40 sx + 1 Hull, Max 400%, Shut in @ 100 PSI

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales (Employee of Operator) or (Operator) of above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dane G. Bales

(Address) P. O. Box 187, Logan, KS 67646

SUBSCRIBED AND SWORN TO before me this 26 day of October, 19 98



My Commission Expires: July 17, 2000.

Betty Jane Bittel
 Notary Public Betty Jane Bittel

15-163-01367-00-00

OPERATOR D. G. Hansen

SEC. 20-8-17W

WELL NAME Reeder "A" #1

LOC. SW SW SW

TOTAL DEPTH 3328'

COUNTY Rooks

COMM. March 24, 1959 COMP. April 2, 1959

STATE Kansas

RIG NO. 1

ELEVATION 1898' K.B.

CASING: Ran 175.95 (9 jts.) 8-5/8" OD Surface Casing.

PRODUCTION: Producing

Set 5-1/2" OD Casing @3322' (103 jts.)

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	620	Sand-Shale		
620	775	Shale-Sand		
775	910	Sand		
910	1236	Shale-Red Bed		
1236	1272	Anhydrite		
1272	1700	Shale-Shell		
1700	1780	Shale-Lime		
1780	2015	Shale-Shell		
2015	2350	Shale-Lime		
2350	2500	Lime-Shale	0° - 2500	
2500	2795	Shale-Lime	0° - 2750	
2795	3065	Lime-Shale	0° - 3000	
3065	3120	Lime		DST 3094-3120'
3120	3125	Lime-Shale		DST 3094-3125'
3125	3157	Lime		DST 3138-3157'
3157	3207	Lime-Shale		DST 3204-3221'
3207	3262	Lime	0° - 3250	DST 3230-3262'
3262	3328	Lime-Shale		

STATE OF KANSAS

COUNTY OF SEDGWICK

SS.

4/1/59

RECEIVED
KANSAS CORP. COMM.
APR 1 1959

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 6th day of April, 1959.

My commission expires:
May 20, 1959

Vicky Jacobs
Vicky Jacobs - Notary public