

15-163-20401-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rooks County, Sec. 20 Twp. 8 Rge. 17 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NE NW

Lease Owner Northridge Oil Co.

Lease Name Reeder Well No. 1

Office Address P. O. Box 18271, Denver, Colorado 80218

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 1-5 19 72

Application for plugging filed 1-5 19 71

Application for plugging approved 1-5 19 71


Plugging commenced 1-5 19 71

Plugging completed 1-5 19 72

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3,364 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	261'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole w/heavy mud
Set bridge plug @660'
Pump 70 sax cement on plug thru 4 1/2" drill pipe
Fill hole w/ heavy mud
Set bridge plug @240'
Pump 20 sax cement on plug thru 4 1/2" drill pipe
Fill hole w/heavy mud
Set bridge plug @40' w/1/2 sax hulls on plug
Dump 10 sax cement on plug to cellar

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1972
CONSERVATION DIVISION
Wichita, Kansas

1-20-72

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.

Address Shields Bldg., Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss. R. L. Shields contractor

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. L. Shields, vpres

Shields Bldg., Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 1972

My commission expires May 26, 1975

Ruth Phillips Notary Public.



Shields


15-163-20401-00-000

Russell, Kansas

WELL LOG

Operator: Northridge Oil Company
 Well: Reeder #1
 Commenced: December 26, 1971
 Completed: January 5, 1972
 Contractor: Shields Drilling Co., Inc.

Well Description: NW NE NW
 Sec. 20-8S-17W
 Rooks Co., Kansas



CASING RECORD		
Size	Run	Pulled
8 5/8"	261'	Cmtd. w/175 sax

Elevation:
 Treatment:
 Production: D & A
 Tops:

..... Figures Indicate Bottom of Formations

Rock & Shale	70'
Shale	640'
Shale, sand & redbed	1,282'
Anhydrite	1,318'
Shale & shells	1,950'
Shale & lime	3,105'
Lime	3,364' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 20 1972
 CONSERVATION DIVISION
 Wichita, Kansas
 1-20-72

Notes