


15-163-00695-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rooks County, Sec. 21 Twp. 8 Rge. 7 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Petroleum, Inc.
Lease Name STAMPER 'A' Well No. 1
Office Address 305 East 3rd Street, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 29, 1953
Application for plugging filed December 29, 1953
Application for plugging approved December 29, 1953
Plugging commenced December 29, 1953
Plugging completed December 29, 1953
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3530 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 190' and set wooden plug at
190'. Placed 1/3 sack hulls on top of
plug at 190'. Cemented and displaced
20 sacks cement through drill pipe onto
plug and hulls at 190'. Mudded up to 40'
and set second wooden plug at 40'. Filled
hole to bottom of well cellar with 10
sacks cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company 1-8-54
Address R.R. #2, Great Bend, Kansas.


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. W. Fisher*
305 East 3rd, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 54
Shantelle Mason
Notary Public.

My commission expires October 13, 1954.

24-7368-S 3-53-20M



15-163-00695-00-00

DRILLER'S LOG STAMPER 'A' #1

Petroleum, Inc., Operator

Section 21, Twp. 8S, Rge. 17W

Garvey Drilling Company, Contractor

Location: NW NW SE

Drilling Commenced: December 18, 1953.

County: Rooks County, Kansas.

Drilling Completed: December 29, 1953.

Production: D & A

Casing Record: 8 5/8" @ 200' w/135 sax.

Figures below indicate bottom of formation:

50	Surface Clay & Rock
150	Shale, Sand, & Shells
200	Shale
805	Shale & Shells
1005	Sand
1292	Red Bed, Shale, & Shells
1335	Anhydrite
1800	Shale & Shells
2925	Lime & Shale
3525	Lime
3530	Conglomerate
3530	R.T.D.

Tops:

Heebner:	3088 (-1112)
Lansing:	3129 (-1183)
Conglomerate:	3424 (-1478)

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W. W. Fisher

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 6th day of January, 1954.

Charlotte Merson
 Notary Public

My commission expires: October 13, 1954.

PLUGGING
 FILE SEC 21 T 8 R 17W
 BOOK PAGE 4 LINE 40

18-54