

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20102-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1968
CONSERVATION DIVISION
Wichita, Kansas
04-15-1968

Operator's Full Name C & G Drilling Co.

Complete Address: 1107 Union National Bldg., Wichita, Kansas

Lease Name Maddy Well No. 1

Location NE SE SE Sec. 12 Twp. 8 Rge. 18 (E) (W) X

County Rooks Total Depth 3425

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 8:15 P Day 11 Month 4 Year 1968

The Above well was plugged as follows:

RTD 3425' 8 5/8 csg set at 176' cwc 125 sc. Cem. Mat. 100 sc 50-50 Poz cem W/6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 150' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leo F. Wasey*
Well Plugging Supervisor

DATE 4/15/68
INV. NO. 4578-4