

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-22-1981

API Number 15-163-21, 50200-09

200 Colorado Derby Building
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name BLACK PETROLEUM INC

Complete Address #345 - OLIVER WEST - GARVEY BLDG. WICHITA, KANS.

Lease Name CONYAC Well No. #1

Location 150' W - SE - NE - NW Sec. 12 Twp. 8 Rge. 18 (East)(West)

County ROOKS. Total Depth 3450^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor SHIELDS DRILLING, INC. (ED WEILER)

Address SHIELDS BLDG., BRUSSEL, KANS. License No. _____

Operation Completed: Hour: 3:15 PM Day: 17th Month: DEC Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 248^{FE} SR. CUL w/ 165ST CIMMON - QUICK SET. (By ALLIED)

ORDERED 135ST 50/50 FORTMIX - 4% GEL - 3% CA-CL & 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST Plug. @ 820 FE w/ 70ST CMT.

2ND Plug. @ 240 FE w/ 40ST CMT.

3RD Plug -> SAND BRIDGE @ 40^{FE} TO w/ 10ST CMT

10ST IN RAT HOLE

5ST IN MOUSE HOLE. (CIR)

CEMENTED BY ALLIED CMT.

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

Signed: Walter Schmidt
Conservation Division Agent

DATE 12-21-82
INV NO. 9039-U