

DISTRICT CONSERVATION AGENT'S REPORT

15-163-03815-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 87-27

LOCATION NE NE SE

SEC. 18 TWP. 8 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Sweet

Operator Westgate Greenland Address Wichita, Kans

Field _____ County Rooks

Total Depth 3489 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 169' circulated with cement - 5 1/2" at 3425'
with 75 sax cement behind.

Filled with chat to 3400', set 4 sax cement with dump bailer,
pulled 2800' 5 1/2", filled with mud to 169', set rock and
15 sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

PLUGGING
FILE REC 18 T 8 R 18w
PAGE 87 LINE 27

4-17-53
RECEIVED
STATE CORPORATION COMMISSION
APR 17 1953
CONSERVATION DIVISION
WICHITA, KANSAS

Edwin Kelly
District Conservation Agent
Date 4-14-53