

6 040280

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22,112 ⁰⁰⁻⁰⁰ *R*
NE SW SW, SEC. 6, T 7 S, R 25 W/E XX

990 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5273

Lease Name Shughart Well # 1

Operator: Kiowa Exploration Company

County Graham 127.40

Name & Address 110 S. Main Suite 510

Well Total Depth 3920 feet

Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 343 w/245 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address Wichita, Ks.

Company to plug at: Hour: AM Day: 29 Month: November Year: 19 84

Plugging proposal received from Bill Craig

(company name) Abercrombie Drilling, Inc. (phone) _____

were: Order 200 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk hulls and 8⁵/₈" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: Noon Day: 29 Month: November Year: 19 84

ACTUAL PLUGGING REPORT

- 1st plug @ 2200 w/40 sks
- 2nd plug @ 1350 w/100 sks 1 sk hulls
- 3rd plug @ 360 w/40 sks
- 4th plug @ 40 w/10 sks
- 10 sks in Rat Hole

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1984
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: _____ (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-13-84

Signed Dennis L. Hamel 27
(TECHNICIAN) 12-1-84

INV. NO. 5967