

4-032028

11-30

00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-21,071

S2 S2 SE /4 SEC. 06, 07 S, 25 W
330 feet from S section line
1320 feet from E section line

Operator license# 5364

Lease Madella well # 1

Operator: Beren Corporation

County Graham

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3910 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 308 feet

127.08

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 30 Month: November Year: 94

Plugging proposal received from: Paul

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 300 sxs. 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 08 1994
CONSERVATION DIVISION
WICHITA, KS
12-8-94

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 9:30A.M., Day: 30, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 308' w/225 sxs. cwc. 5 1/2" set @ 3958' w/200 sxs. D.V. set @ 2140' cwc. w/375 sxs. P.B.T.D. 3882'. Squeezed 2128' - 2145' w/135 sxs. Tested 8 5/8" with 1/2 bbl. water to Max. P.S.I. 500# cement at surface. Squeezed 5 1/2" with 300 sxs. cement blend w/500# hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 1000#. Plug complete.

Remarks: Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: GL

I did / did not observe the plugging. Carl Goodrow

INVOICED
DATE 12-9-94
41878

(agent)
Form CP-2/3