

15-065-00647-00-01

11-30

4-032031

D-25,654

API number: 15- - 1979

TG:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE NE /4 SEC. 07, 07 S, 25 W
4950 feet from S section line
330 feet from E section line

Operator license# 5363 Lease Best well # 3

Operator: Berexco, Inc. County Graham

Address: P.O. Box 723 Well total depth 3880 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 252 feet

126.10

Aband. oil well __, Gas well __, Input well __, SWD X, D & A __

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 30 Month: November Year: 94

Plugging proposal received from: Paul

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 325 sxs. 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 08 1994
12-8-1994
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 10:30A.M., Day: 30, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 252' cwc. 5 1/2" set @ 3879' w/200 sxs. D.V. at 2135' cwc. w/425 sxs. Prod. perfs. 3818' - 3838'.

Squeezed 5 1/2" w/275 sxs. cement blend w/350# hulls mixed in to Max.

P.S.I. 1000#. Close in P.S.I. 1000#. Squeezed 8 5/8" w/50 sxs. cement blend w/150# hulls to Max. P.S.I. 150#. Close in P.S.I. 150#.

Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD __ Anhy. plug: YES X NO __

Bottom plug(in place): YES __, CALC X, NO __ Dakota plug: YES X, NO __

Plugged through TUBING __, CASING X. Elevation: __ GL

I did X] did not [] observe the plugging. Carl Goodrow

INVOICED
DATE 12-9-94
INV. NO. 41893

AD

(agent)
Form CP-2/3