

25W

6 031167 15065-9-19 01311-00-00
API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C S/2 SW SE, SEC. 7, T 7 S, R 25 W/E

330 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Brandt Well # F 2

Operator: Beren Corp
Name & Address: Box 723
Hays, Ks. 67601

County Graham 124.70
Well Total Depth 3837 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Hays, Ks.

Company to plug at: Hour: PM Day: 19 Month: Sept Year: 19 88

Plugging proposal received from Bob Grant

(company name) Beren (phone)

were: 8 5/8" set at 294' cwc 5 1/2" set at 3869'. Perf 3686' - 89'
Perf 3686' - 89' 3831' - 35'. Squeeze 2350' - 3100' Holes at 800' - 1500'.

Order 350 sks 60/40 Poz 8% Gel and 100 sks 65/35 Poz 10% Gel 2% C C exc. 700#

B. J. Titan Cement Co. Joe Newman Water Trucks

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1988

10-21-88

Plugging Proposal Received by David Wann (TECHNICIAN)

Plugging Operation attended by Agent?: All Part None

Operations completed: Hour: 7:45PM Day: 19 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing to bottom. Pump down tubing 100 sks 65/35 10%

Cement Blend w/400# Hulls. Lay down 2000' of tubing, circulate 160 sks Cement Blend 60/40 Poz 8% Gel. Lay down tubing. Squeeze 5 1/2" to max psi 900#. Close in psi 400# w/65 sks Cement Blend. Backside annulus 8 5/8". Tested to max psi 900#w/100 sks Cement Blend. Close in psi 400#. Plug complete.

Remarks: Cement Circulated on backside.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby agree to serve this plugging.

DATE 10-24-88

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

INV. NO. 22660

NOV 15 1988