

11-30

4-032030

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-21,023 <sup>00-00</sup>

C N2 NE /4 SEC. 07, 07 S, 25 W  
4620 feet from S section line  
1320 feet from E section line

Operator license# 5363

Lease Best well # 2

Operator: Berexco, Inc.

County Graham

Address: P.O. Box 723  
Hays, Kansas 67601

Well total depth 3894 feet <sup>126.56</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 326 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 30 Month: November Year: 94

Plugging proposal received from: Paul

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 325 sxs. 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 08 1994  
CONSERVATION DIVISION  
WICHITA, KS

12-8-94

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[     ], Part[ X ], None[     ]

Completed: Hour: 12:00P.M., Day: 30, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 326' w/225 sxs. cwc. 5 1/2" set @ 3894' w/200 sxs. 2 staged w/500 sxs. cwc. from 2140'. Squeezed 8 5/8" w/10 sxs. cement blend to Max. P.S.I. 400#. Close in P.S.I. 400#. Squeezed 5 1/2" w/315 sxs. cement blend w/500# hulls to Max. P.S.I. 1000#. Close in P.S.I. 1000#. Plug complete.

Remarks:      
Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL

I did X observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

INVOICED  
DATE 12-9-94  
INV. NO. 41868