

4-032010

11-2

E-18,445

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -

NW SW SE /4 SEC. 07, 07 S, 25 W
990 feet from S section line
2310 feet from E section line

Operator license# 5363

Lease Brandt "F" well # 1

Operator: Berexco, Inc.

County Graham

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 4340 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 265 feet

141.05

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 2 Month: November Year: 94

Plugging proposal received from: Paul Breining

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 250 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 10 1994
11-10-1994
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:10A.M., Day: 2, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 265' w/150 sxs. cwc. 5 1/2" set @
4214' w/150 sxs. P.B.T.D. 4187'. Prod. perms. 3720' - 3724'. C.I.B.P.
@ 3785. Perf. 3802' - 3826'. D.V. Tool 2040' w/400 sxs. cwc. Squeezed
at 2150' w/150 sxs. Shot @ 1375'. Squeezed 5 1/2" w/250 sxs. cement
blend w/500# hulls mixed into Max. P.S.I. 800#. Close in P.S.I. 100#.
Cement at surface in 8 5/8". Plug complete.

Remarks:
Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES , CALC X, NO Dakota plug:YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did [X] / did not [] observe the plugging. Carl Goodrow

INVOICED
DATE 11-29-94
INV. NO. 41748

HD (agent)