

4-032033

11-30

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-20,862 ⁰⁰⁰⁰

NW /4 SEC. 07, 07 S, 25 W
3190 feet from S section line
2920 feet from E section line

Operator license# 5363

Lease Elmer well # 1

Operator: Berexco, Inc.

County Graham

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3865 feet ^{125.61}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 252 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 30 Month: November Year: 94

Plugging proposal received from: Paul

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 250 sxs. 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 08 1994
CONSERVATION DIVISION
WICHITA, KS
12-8-94

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 1:15P.M., Day: 30, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 252' w/225 sxs. cwc. 4 1/2" set @ 3864' w/100 sxs. P.B.T.D. 3834'. Prod. perfs. 3672' - 3824'. Critical area control shots at 1350' and 2130'. Squeezed 8 5/8" w/50 sxs. cement blend w/100# hulls mixed in to Max. P.S.I. 100#. Close in P.S.I. 100#. Squeezed 4 1/2" w/200 sxs. cement blend w/400# hulls to Max. P.S.I. 250#. Close in P.S.I. 100#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD Any plug: YES X NO

Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: GL

I did X did not [] observe the plugging. Carl Goodrow

INVOICED

DATE 12-9-94

INV. NO. 41871

HO- (agent)