

4-032029

11-30

00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-20,802

NE SW NE /4 SEC. 07, 07 S, 25 W
3630 feet from S section line
1650 feet from E section line

Operator license# 5363

Lease Best well # 1

Operator: Berexco, Inc.

County Graham

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3850 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 282 feet

125.13

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 30 Month: November Year: 94

Plugging proposal received from: Paul

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 275 sxs. 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 08 1994
CONSERVATION DIVISION
WICHITA, KS
12-8-94

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 12:30 P.M., Day: 30, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 282' w/180 sxs. cwc. 4 1/2" set @ 3849' w/100 sxs. Squeezed at 1420' w/200 sxs. - critical area control shots at 1325' and 2125'. P.B.T.D. at 3814'. Prod. perfs. 3794' - 3798'. Squeezed 8 5/8" w/75 sxs. cement blend w/100# hulls to Max. P.S.I. 300#. Close in P.S.I. 100#. Squeezed 5 1/2" casing w/200 sxs. cement blend w/400# hulls to Max. P.S.I. 500#. Close in P.S.I. 100#. Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING _____, CASING . Elevation: _____ GL

I did did not observe the plugging. Carl Goodrow

DATE 12-9-94
INV. NO. 41869

(agent)
Form CP-2/3