

4-19

14 R

4-060385 15-065-19071-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 4-8-55

SE SE SW /4 SEC. 07 , 07 S, 25 W
330 feet from S section line
2970 feet from E section line

Operator license# 5364 Lease Huntington well # 1

Operator: Beren Corporation County Graham

Address: P.O. Box 723 Well total depth 3870 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 272 feet

125.77

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 11:00A.M Day: 19 Month: April Year: 93

Plugging proposal received from: Bob Grant

Company: Beren Corporation Phone: 913-628-6101

Were: Order 225 sxs. 65/35 posmix - 10% gel. and hulls.
Packer and 3 joints of tubing stuck at 3781'. Hole in casing at 1739'.
Anhydrite 2135' - 2168'. Well outside of Wellington salt area.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:30P.M., Day: 19, Month: April, Year: 93

Actual plugging report: 8 5/8" to 272'. 5 1/2" to 3868'. Squeezed
at 1319' - 1349' with 180 sxs. Squeezed holes at 2230' - 2460' with
200 sxs. Squeezed hole at 3220' with 115 sxs. Perfs from packer - 3854'.
Ran tubing to 2200' and pumped 50 sxs. cement. Pulled tubing to 1715'
and pumped 50 sxs. cement. Pulled tubing to 1211' and circulated cement
to surface with 60 sxs. cement. Pulled tubing and tied onto annulus.
Mixed and pumped 40 sxs. cement and 100# hulls. Tied onto production
casing and pumped 95 sxs. cement. Max. 900#. Standing S.I.P. 800#.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 2570 GL

430-93

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1993

I did X did not [] observe the plugging.

(agent) CONSERVATION DIVISION
Wichita, Kansas
Form CP-2/3

INVOICED

DATE 5-3-93

NO. 37642