

6 031257

5-2579-005-02971-00-00
12 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Oxy USA Inc.
Name & Address Box 38
Hill City, Ks. 67642

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cement Co. License Number _____

Address Oberlin, Ks.

Company to plug at: Hour: _____ PM Day: 25 Month: May Year: 19 89

Plugging proposal received from Pringle

(company name) Oxy USA (phone) _____

were: 8 5/8" set at 238' w/225 sks cwc 5 1/2" set at 3889' w/175 sks. PBD 3650'.

Perfs 3690' - 3855'. D.V. tool at 2184' w/475 sks cwc. Order 300 sks 65/35 Poz 10% gel
400# Hulls. Halliburton Cement Co. Wellbrock Water.

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1989
6-21-89
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4:45PM Day: 25 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/50 sks common cement, followed w/260 sks
cement b lend and 350# hulls to max psi 1000#. Close in 850#. Tested 8 5/8" to 400# w/no
cement. Plug complete.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I () did not observe this plugging.

DATE 6-23-89
INV. NO. 25112

Jib S

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow