

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22185-00-00
Spot: S2SWNWSW Sec/Twnshp/Rge: 17-7S-25W
1590 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: MYERS-BROWN Well Number: 3
County: GRAHAM Total Vertical Depth: 3950 feet

Operator License No.: 31147
Op Name: D & L ENERGY
Address: HCR-01 BOX 99
MORLAND, KS 67650

Conductor Pipe: Size feet: 128.38
Surface Casing: Size 8.625 feet: 343
Production: Size 4.5 feet: 3940
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/19/2001 1:00 PM
Plug Co. License No.: 31147 Plug Co. Name: D & L ENERGY
Proposal Rcvd. from: LEROY Company: D & L ENERGY Phone: (785) 627-5401

Proposed Plugging Method: Order 400 cu.ft. of cement slurry.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/19/2001 2:30 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 343' w/285 sxs cwc.
4 1/2" set at 3940' w/455 sxs cwc.
Prod. Perfs 3741' - 3793' O.A.
4 1/2" casing was dry to T.D.
Filled 4 1/2" casing with 400 cu.ft. of cement slurry.
Plug complete.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 10 2002
1-10-2002
CONSERVATION DIVISION

Remarks: 60'S.SWNWSW 17-07-25W.

Plugged through: CSG

District: 04

Signed Carl Goodrow (TECHNICIAN) KCC


INVOICED JAN 08 2002

DATE Jan 11, 02 HAYS, KS

INV. NO. 2002061239

JAN 02 2002

BOB MYERS
 11945 FOREST WOOD DRIVE #3 MYERS-BROWN 17-7-25W
 DALLAS, TX 75234 60'S.
 CONTR ABERCROMBIE DRILLING CTY GRAHAM C SW NW SW
 GEOL BEN LANDES FIELD BLAZIER NW
 ELV 2595 KB SPD 5/10/85 CARD ISSUED 8/15/85 IP P 10 BO & 28 BWPD
 2590 GL DRLG COMP 5/16/85 LKC 3741-3793 OA



SMP	Tops	Depth/Datum	API 15-065-22, 185
ANH	2196+ 399	8 5/8 " 343 / 285SX, 4 1/2 " 3940 / 455SX
HEEB	3675-1080	DST (1) 3726-45 (LKC) / 30-60-30-60, REC 5' SOCM (3% OIL, 97% M), SIP 846-721#, FP 38-48 / 48-48#, HP 1916-1877#
TOR	3699-1104	DST (2) 3745-84 (LKC) / 30-60-30-60, REC 5' VSOCM, SIP 365-268#, FP 48-58 / 58-58#, HP 1959-1930#
LANS	3714-1119	DST (3) 3784-3806 (LKC) / 30-60-30-60, REC 5' FREE OIL, 60' SOCM (5% OIL, 95% M), SIP 625-548#, FP 67-77 / 88-96#, HP 2019-1949#
BKC	3910-1315	DST (4) 3806-74 (LKC) / 30-60-60-90, REC 20' SOCM, SIP 873-854#, FP 60-60 / 70-70#, HP 2019-1948#
RTD	3950-1355	MICT - CO, PF (LKC) 1 / 3868, 1 / 3832, AC 2800G (15% NE), SWB DWN, NON-COMMERCIAL, PF (LKC) 3790-93, W / 2 SPF, AC 250G (15% MA), SWB DWN, RE-AC 1500G (15% NE), SWB DWN, SO, PF (LKC) 3741-44, W / 3 SPF, AC 1500G (15% NE), SWB DWN, RE-AC (3790-93, 3741-44), -W / AC 10,000G (15% NE), SWB DWN, SO, SET 2 3/8 " TBG AT 3801, POP, P 10 BO & 28 BWPD (GR 39°), 6/10/85