

15-065-02322-00-0

5-25

NO C

81

6 031259

API NUMBER 15- 1956

E9707

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW NW, SEC. 27, T 7 S, R 25 W/E

4290 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Blazier Unit Well # 401 W

Operator: Oxy USA Inc.
Name & Address: Box 38
Hill City, Ks. 67642

County Graham 126.75

Well Total Depth 3900 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 235

Abandoned Oil Well Gas Well Input Well x SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cement Co. License Number

Address Oberlin, Ks.

Company to plug at: Hour: AM Day: 25 Month: May Year: 19 89

Plugging proposal received from Pringle

(company name) oxy USA (phone)

were: 8 5/8" set at 235' w/225 sks. 4 1/2" set at 3884' w/200 sks. PBTB 3871'.

D.V. tool at 2141' w/500 sks. Perf 3689' - 3789'. Order 300 sks 65/35 poz 10% gel 50 sks

common cement 300# Hulls. Halliburton Cement Co. Wellbrock water.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part x None

Operations Completed: Hour: 11:00AM Day: 25 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 4 1/2" w/50 sks common cement chased with 170 sks cement blend w/300# hulls mixed into max psi 400#. Close in 150#. Squeezed backside w/ 60 sks cement blend to max 300# close in 200# psi. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

JUN 26 1989 6-26-1989 CONSERVATION DIVISION Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED did not observe this plugging.

DATE 6-27-89

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 25134

Carl Goodrow