

6 030595

API NUMBER 15-065-22,253-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SUNWINE SEC. 25 T. 7 S. R. 25 (W)

4290 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4655

Lease Name BARNET Well # 1-25

Operator: BHP PETROLEUM INC.
(AMERICAS)

County GRAHAM 129.03

Name & Address 925 PATTON ROAD

Well Total Depth 3970 feet

GREAT BEND, KANSAS

Conductor Pipe: Size _____ feet

67530

Surface Casing: Size 8 5/8 feet 262'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor RED TIGER DRUG. CO. License Number 5302

Address WICHITA KANSAS

Company to plug at: Hour: AM Day: 31 Month: 10 Year: 19 85

Plugging proposal received from KENNETH

(company name) RED TIGER (phone) _____

were: 8 5/8 SET @ 262' w/200SX. WITH HOLE FULL OF NO LESS THAN 36UIS
MUD AND NO LOSS OR GAIN OF FLUID SPOT CEMENT PLUGS WITH
DRILL PIPE. ORDER 190 SX. 60/40POZ 6% GEL 3% CC 8 5/8 W.P.
HALLIBURTON CMT. CO.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:45AM Day: 31 Month: 10 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P @ 2150 DISPLACE 25 SX. CMT. MIX. LAYDOWN
D.P. TO 1300' DISPLACE 100 SX. CMT. MIX + 1 SX. HULLS LAYDOWN D.P.
TO 265' DISPLACE 40 SX. CMT. MIX. LAYDOWN D.P. PUSH W.P. TO
KELLY DEPTH DUMP 1/2 SX. HULLS AND 10 SX. CMT. MIX TO BASE CELLAR
DISPLACE 15 SX. CMT MIX IN RAT HOLE W/JOINT OF PIPE. PLUG COMPLETE.

Remarks: ELEV. 2464 KB ANHY 2138-72' POND WATER
(If additional description is necessary, use BACK of this form.)

INVOICED (I did not observe this plugging)

DATE NOV 25 1985

NOV 20 1985

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 11195

DEC 13 1985

11-20-85