

11-2 4-032009 15-065-19075-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- -  
NW 1/4 SE NW NE /4 SEC. 18, 07 S, 25 W  
4950 feet from S section line  
2310 feet from E section line

Operator license# 5363 Lease Brandt well # 2

Operator: Berexco, Inc. County Graham

Address: P.O. Box 723 Well total depth 4175 feet  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 150 feet

135.69

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 2 Month: November Year: 94

Plugging proposal received from: Paul Breining

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 300 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 10:00A.M., Day: 2, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 150' w/100 sxs. cwc. 5 1/2" set @  
3900' w/100 sxs. P.B.T.D. 3777'. Prod. perfs. 3688' - 3738'. C.I.B.P.  
@ 3785. Perf. below 3812' - 3840'. Squeezed at 1650' w/250 sxs.  
T.O.C. by log 1120'. Squeezed 5 1/2" w/250 sxs. cement blend w/450#  
hulls mixed into Max. P.S.I. 800#. Close in P.S.I. 800#. Squeezed  
8 5/8" w/50 sxs. to Max. P.S.I. 100#. Close in P.S.I. 100#.

Remarks: Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL

I did X [ ] did not [ ] observe the plugging. Carl Goodrow

DATE 11-29-94

(agent) 11-10-94

INV. NO. 41749

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 10 1994  
CONSERVATION DIVISION