

PLUGGED

90 2

6 070494

API NUMBER 15-~~DU5~~-22308-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE-SW 1/4, SEC. 17, T. 7 S, R. 25 W 1/4
392.5 FEET
445 FEET

TECHNICIAN'S PLUGGING REPORT

Operator License # 9542

Operator: Robert W. Myere
Name & Address: 11945 Forest Wood Dr.
Dallas, Texas. 75244
Robert Myere

392.5 FEET feet from S section line
525 FSL feet from E section line

Lease Name Myers Brown Well # 4

County McPherson 128.31

Well Total Depth 3948 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 321

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address Plainville, Kansas. 67663

Company to plug at: Hour: 10:00 AM Day: 15th Month: July Year: 1986

Plugging proposal received from Jeroy Cline

(company name) Seith Operations (phone) 316-193-8636

were: 8 5/8" - 321 ft csc #190^{SK} cmt, 4 1/2" cog set @ 3946 FT #125^{SK} cmt.

Plug Back T.O. 3922 FT, Perfs 3863' - 3693', shot log 3 times

th. Bottom Sand Perfs to 3640 FT and #4^{SK} cmt. (Recovered 1515')

Proposal - Order 160^{SK} 60/40 Permox 6% Gel - 3% CaCl. - 5^{SK} shells, 7 8 5/8" Plug.

Pump in 8 5/8" S.P. with Pump Truck, Pump In 20^{SK} cmt, 12^{SK} gel, 3 1/2^{SK} shells,

10^{SK} cmt, 18^{SK} gel - 1/2^{SK} shells Plugging Proposal Received by MJ Schmidt (TECHNICIAN)

Rel. Plug and 70^{SK} cmt.

Plugging Operations attended by Agent? All Part None

Operations Completed: Hour: 11:15 AM Day: 15th Month: July Year: 1986

ACTUAL PLUGGING REPORT Ordered 160^{SK} 60/40 Permox 6% Gel - 3% CaCl, 5^{SK} shells

and 8 5/8" Plug, (shot log 3 times 2400' - 1915' T 1515' Recovered 1515'

Pumped in 8 5/8" cog, 20^{SK} cmt, 12^{SK} Gel,

3 1/2^{SK} st. shells, 48^{SK} cmt, 18^{SK} Gel, 1/2^{SK} shells,

Release Plug and 70^{SK} cmt.

Cemented by Allied Cementing, Plainville, Mo. (Guy)

Remarks: _____

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

DATE 7-21-86

WV. NO. 14407

Signed MJ Schmidt (TECHNICIAN) 8-17-86

7-15 AUG 29 1986

7-18-1986
JUL 18 1986
SEP 29 1986