

11-2 4-032011 15-065-01312-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -

SE NE NW /4 SEC. 18 , 07 S, 25 W
4290 feet from S section line
2970 feet from E section line

Operator license# 5363 Lease Moore well # 1

Operator: Berexco, Inc. County Graham

Address: P.O. Box 723 Well total depth 3905 feet ^{126.91}
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 275 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 2 Month: November Year: 94

Plugging proposal received from: Paul Breining

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 300 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:40P.M., Day: 2, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 275' w/175 sxs. cwc. 5 1/2" set @
3904' w/125 sxs. P.B.T.D. 3860'. Prod. perfs. 3765' - 3775'. 5 1/2"
holes squeezed 2280' - 2330' - 2345' - 2400' - 2979' - 3175' w/500 sxs.
Shot @ 1375'. Squeezed 5 1/2" w/225 sxs. cement blend w/450# hulls to
Max. P.S.I. 800#. Close in P.S.I. 500#. Squeezed 8 5/8" w/75 sxs.
cement blend w/50# hulls to Max. P.S.I. 100#. Close in P.S.I. 100#.
Plug complete.

Remarks: Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES , CALC X, NO Dakota plug:YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did observe the plugging. Carl Goodrow

INVOICED

DATE 11-29-94

INV. NO. 41751

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1994
CONSERVATION DIVISION
WICHITA, KANSAS

11-10-94