

11-2

4-032012

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-005-01695-0000

NW NW NE /4 SEC. 18 , 07 S, 25 W  
4950 feet from S section line  
2310 feet from E section line

Operator license# 5363

Lease Brandt well # 3

Operator: Berexco, Inc.

County Graham

Address: P.O. Box 723  
Hays, Kansas 67601

Well total depth 3925 feet <sup>127.56</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 291 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: J.B. Well Service License# 3160 TAG

Address: McCook, Nebraska

Company to plug at: Hour: P.M. Day: 2 Month: November Year: 94

Plugging proposal received from: Paul Breining

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 300 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 8:00P.M., Day: 2, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 291' w/150 sxs. cwc. 5 1/2" set @ 3924' w/100 sxs. P.B.T.D. 3890'. Prod. perfs. 3727' - 3874'. Critical area control shots at 2180' and 1375'. Squeezed 5 1/2" with total of 300 sxs. cement blend with 440# hulls to Max. P.S.I. 500#. Close in P.S.I. 300#. Squeezed 8 5/8" w/100 sxs. cement blend w/100# hulls to Max. P.S.I. 400#. Close in P.S.I. 200#. Plug complete.

Remarks: Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO  
Bottom plug(in place):YES ,CALC X ,NO Dakota plug:YES X ,NO  
Plugged through TUBING , CASING X . Elevation: GL

I did X observe the plugging. Carl Goodrow

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 10 1994  
CONSERVATION DIVISION

11-10-94

INVOICED

DATE 11-29-94  
INV. NO. 41750

(agent)  
Form CP-2/3